BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer
DTS COPY

NAME OF WORK: Providing Street Name Board at Ravindrannagara & Mallasandra, in Ward no.13 in Shettyhalli Sub-Division

Sl. No	Description of work	Unit	Qty	Tender Rate	
				In Figures (Rs.)	In Words (Rs.)
1	3	4	2	5	6
1	Earthwork excavation for foundation of buildings, water supply, sanitary, lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications.	Cum	73.15		
2	Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @0.465cum machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	30.86		
3	Providing fabricating fixing MS name board of size 0.9x0.6 mts, with vertical post of 3.70 mtr height made out of two jointly welded 65x65x6mm angles, with necessary hold fast weld top, name board of 18guage sheet of size 0.9x0.6mts welded to angles of 25x25x4mm on all sides with all fabrication charges, transportation & other incidential charges.	Nos	254.00		
4	Providing and applying two coats of ready mix paint of approved brand after through cleaning of surface to give an even shade complete as per specifications.	Sqm	879.86		
5	Painting New letter and figures of any shade with synthetic enamel paint black of any other approved colour to give an even shade complete as per specifications.	Cm	162560.00		

Signature of the Contractor

Number Of Corrections:- Nil

Executive Engineer,
Dasarahalli Division,

D.T.S.
is Approved

ದಾಸರಹಳ್ಳಿ ವಲಯ.